



PURPOSE

The purpose of this policy is to outline the inspection and testing methods used during the installation of a fire alarm system.

POLICY

Fire alarm systems shall be installed and tested in accordance with the Arkansas Fire Prevention Code referencing applicable NFPA 72 Standards.

Fire alarm plans shall be reviewed by members of the Fire, Building & Safety Division.

Fire alarm systems shall be inspected and tested by the following:

1. Initiation and notification device locations (Visual)
2. Main fire panel location
3. Remote annunciator location
4. Strobe candelas accordance to design
5. Audible decibels accordance to design
6. Voice evac intelligibility
7. Smoke / heat / CO detectors
8. Mechanical shutdowns
9. Battery backup
10. Central station supervision
11. Connected to kitchen hood suppression
12. FA system keys available
13. FA system breaker identified at electric panel
14. System installer identified
15. Monitoring company identified
16. Knox box location
17. Complete inspection report

Approved